



Mihos.net Datacenter Specifications

GENERAL

- Year of construction: 2010
- Gross surface: 800m²
- Above sea level: data floor, offices

SECURITY

- Security: 24x7 staffed
- Cameras: HD infrared cameras
- Access control: badge and fingerprint system

POWER

- Rack feeds: separated A and B feed (32A)
- Diesel stock: 48+ hours, refillable during use
- UPS: 15+ minutes runtime
- Redundancy: N+2

COOLING

- Constant temperature: 21 Celsius
- Humidity: 50% (+/- 20%)
- Redundancy: N+2

FIRE PREVENTION

- Fire detection system: VESDA
- Fire suppression system: Argonite gas
- Redundancy: N+1

INTERCONNECTION

Mihos.net datacenter is carrier neutral.

- Available fiber networks:
KPN, Relined, Eurofiber, UNET
- Available transits:
Mihos.net, Atom86, UNET, Fiberring

CERTIFICATIONS

- ISO Certified
ISO 9001:2015
ISO 27001:2013
- PCI DDS compliant
- 100% green energy